Calling Attention to a Matter of Urgent Public Importance
re: breakage of sluice of Sira Doddakere

Sri BOLA RAGHURAM SHETTY (Karkal).—I call the attention of the Minister of State for Minor Irrigation to the breakage of sluice of Sira Doddakere.

† Smt. BASAVARAJESWARI (Deputy Minister for Social Welfare).—Sira Doddakere is a major tank bearing Register No. 2 and Sl. No. 152, and has got a total atchkat of 814 acres and 32 guntas (633 acres 1 gunta of wet and 211 acres 31 gnntas of garden). The tank has got only one masonry wasteweir and the same is in good condition. This tank has got in all three sluices. The front cistern of the left sluice being in a dilapidated condition required some urgent repairs. Hence, an estimate for Rs. 1,200 for reconstruction of this cistern was sanctioned by the Executive Engineer, Madhugiri Division, and the work was to be taken up for execution. Meanwhile the front slab of the cistern was damaged by some of the ryots in order to draw water from the tank at a level lower than cill level of the plug sluice. As a result of this, there was some leakage from the sluice when the tank received water due to rains on the night of 24th August 1969. On receipt of this information immediate action was taken by the Executive Engineer to prevent leakage of water through the sluice by replacing the broken front slab of the cistern of the sluice. Action was also taken to block the leakage by putting puddle and sand bags. It is reported that the leakage was stopped and at present there is no wastage of water through the sluice. The tank has now received water during the recent rains, hence the proposed reconstruction of front cistern of the sluice cannot be taken up now. However, the Executive Engineer has taken necessary action to get repairs done to the sluice immediately the water level in the tank were to go down.

ಶ್ರೀ ಬೋಳಾ ರಘುರಾಮ ಶೆಟ್ಟಿ.—ಈ ಕೆರೆಯ ಸ್ಲೂಯಿಸ್ ಒಡೆದು ಸುಮಾರು ಐದು ತಿಂಗಳಾದವು. ಈ ಸಂದರ್ಭದಲ್ಲಿ ಪಿ.ಡಬ್ಲ್ಯು.ಡಿ. ಇಂಜನೀಯರವರು ನೀರು ಹೋಗಲು ಸ್ಲೂಯಿಸ್‌ನ್ನು ಓಪನ್ ಮಾಡಿದರು ಇದರಿಂದ ರೈತರು ನೀರಾವರಿಗೆ ಉಪಯೋಗ ಮಾಡಲೂ ಆಗಲಿಲ್ಲ ಮತ್ತು ಸುಮಾರು 250 ಎಕರೆ ಸಾಗುವಳಿಯಾಗುವುದೂ ಹೋಯಿತು. ಆದುದರಿಂದ ಇದರ ಬಗ್ಗೆ ಅಕ್ರಮವಾಗಿ ಕೆಲಸ ಮಾಡಿದ ಅಧಿಕಾರಿಗಳಮೇಲೆ ಏನು ಕಾರ್ಯಕ್ರಮ ತೆಗೆದುಕೊಳ್ಳುತ್ತೀರಿ ಮತ್ತು ಇದನ್ನು ಸರಿ ಮಾಡಲು ಇನ್ನೆಷ್ಟು ಕಾಲ ತೆಗೆದುಕೊಳ್ಳುತ್ತೀರಿ?

ಶ್ರೀಮತಿ ಬಸವರಾಜೇಶ್ವರಿ.—ನೀರು ಹೆಚ್ಚಾಗಿ ಬಂತು ಎಂದು ಇಲ್ಲಿ ಮೊದಲು ಸ್ಲೂಯಿಸ್‌ನ್ನು ಒಡೆಯಲು ಅಧಿಕಾರಿಗಳು ಅವಕಾಶ ಕೊಟ್ಟಿದ್ದರು. ಆದರೆ ಕೆರೆ ನೀರು ತುಂಬಿದ ಕೂಡಲೇ ಇದರಲ್ಲಿ ಲೀಕೇಜು ಇರುವುದು ಗೊತ್ತಾಯಿತು. ಆದರೆ ಇಲ್ಲಿನ ಅಸಿಸ್ಟೆಂಟು ಇಂಜನೀಯರು ಬಹಳ ತೀವ್ರಗತಿಯಿಂದ ತಕ್ಕ ಕೆಲಸ ಮಾಡದೇ ಇದ್ದುದರಿಂದ ಇಲ್ಲಿಯ ನೀರನ್ನು ಸರಿಯಾಗಿ ಉಳಿಸರಾಗಲಿಲ್ಲ. ಆದರೆ ಇಲ್ಲಿರುವ ಎಕ್ಸಿಕ್ಯೂಟೀವ್ ಇಂಜನೀಯರು ಬೇಗನೆ ತಕ್ಕ ಕಾರ್ಯಕ್ರಮವನ್ನು ತೆಗೆದುಕೊಂಡಿದ್ದಾರೆ. ಇದರಲ್ಲಿ ಸ್ಯಾಂಡ್ ಬಾಗ್ಸ್ ತಂದು ಹಾಕಿದ್ದಾರೆ ಮತ್ತು ಲೀಕೇಜುಗಳನ್ನು ದುರಸ್ತು ಮಾಡಿದ್ದಾರೆ. ಇದರ ಬಗ್ಗೆ ಒಂದು ಅಂದಾಜು ಮತ್ತು ಎಕ್ಸ್‌ಪರ್ಟ್ ರಿಪೋರ್ಟು ಇವೆರಡ್ನೂ ಬರುವುದರಲ್ಲಿವೆ. ಕೆರೆಯ ನೀರು ಕಡಿಮೆಯಾದಮೇಲೆ ಇಲ್ಲಿ ಸೂಕ್ತ ಕ್ರಮ ಕೈಗೊಳ್ಳರಾಗುತ್ತದೆ.